



Warewashing Systems

INSTALLATION, OPERATION, AND SERVICE MANUAL



DELTA[®] 5-E

DELTA[®] SERIES GLASSWASHER DISHMACHINES

Delta 5-E Manual • 07610-003-37-08-R

**MANUFACTURER'S LIMITED WARRANTY
(APPLICABLE ONLY IN THE UNITED STATES AND CANADA)**

WARRANTY REGISTRATION:

To register your Jackson Dishmachine's warranty go to jacksonwws.com/warranty or call 1-888-800-5672. Failure to register the Dishmachine will void the warranty.

ONE YEAR LIMITED PARTS AND LABOR WARRANTY

For a period of one (1) year from date of original installation of a new Jackson Dishmachine (but in no event to exceed eighteen (18) months from date of shipment from Jackson's factory), Jackson WWS, Inc. (Jackson) will repair or replace, at its discretion, any original part that proves defective in materials or workmanship at the time the Dishmachine was purchased; provided that (i) the Dishmachine has not been altered, (ii) the Dishmachine has been properly installed, maintained, and operated under normal use conditions and in accordance with the applicable installation, operation and service manual available on the Jackson website, and (iii) a warranty claim is reported to a Jackson Authorized Service Agency within the warranty period. This warranty includes replacement with Jackson specified genuine replacement parts, purchased directly from a Jackson Authorized Parts Distributor or Service Agency. Use of generic replacement parts may create a hazard and shall void this warranty.

THIS WARRANTY DOES NOT APPLY OUTSIDE THE UNITED STATES AND CANADA.

Jackson will pay the labor to repair or replace a defective original part as a part of the warranty, provided that a Jackson Authorized Service Agency performs the labor. Any repair or replacement work by anyone other than a Jackson Authorized Service Agency is the sole responsibility of the purchaser. Labor coverage is limited to regular hourly rates; Jackson will not pay overtime premiums or emergency service charges.

Accessory components (such as table limit switches, pressure regulators, and drain water tempering kits) that are not installed by Jackson at the factory and are shipped with the Dishmachine carry only a (1) one-year parts warranty. Labor to repair or replace these components is not included in the warranty or covered by Jackson. Booster heaters not manufactured by Jackson are not covered by this warranty but are warranted by their respective manufacturers. This warranty is void if any defect or failure is a direct result from shipping, handling, fire, water, accident, alteration, modification, misuse, abuse, flood, acts of God, burglary, casualty, attempted repair by unauthorized persons, use of replacement parts not authorized by Jackson, improper installation, installation not in accordance with local electrical and plumbing codes, if the serial number has been removed or altered, if the Dishmachine is used for any purpose other than originally intended, or if the equipment is installed for residential use.

Jackson does not authorize any other entity or person, including, without limitation, any entity or person who deals in Jackson Dishmachines, to change this warranty or create any other obligation in connection with Jackson Dishmachines.

TRAVEL LIMITATIONS:

Jackson limits warranty travel time to the customer site within 50 miles of the Jackson authorized service agent's office and during regular business hours. Jackson will not pay for travel time and mileage that exceeds these limits, or any fees such as those for air or boat travel without prior authorization.

REPLACEMENT PARTS WARRANTY:

For a period of (90) ninety days from the date of installation by a Jackson Authorized Service Agency (but in no event to exceed (180) one-hundred-eighty days from the date of purchase from a Jackson Authorized Parts Distributor or Service Agency), Jackson will repair or replace, at its discretion, any Jackson genuine replacement parts that prove defective in materials or workmanship at the time the replacement parts were installed. This warranty does not include paying the labor to repair or replace the replacement part. This warranty is subject to all conditions, exclusions and limitations applicable to the Dishmachine.

**MANUFACTURER'S LIMITED WARRANTY (CONT.)
(APPLICABLE ONLY IN THE UNITED STATES AND CANADA)**

PRODUCT CHANGES:

Jackson reserves the right to make changes in design and specification of any component of the Dishmachine as engineering or necessity requires.

DISCLAIMER OF WARRANTIES:

THERE ARE NO WARRANTIES, EXPRESSED OR IMPLIED, INCLUDING, WITHOUT LIMITATION, ANY IMPLIED WARRANTY OF FITNESS FOR A PARTICULAR PURPOSE OR MERCHANTABILITY, THAT ARE NOT SET FORTH HEREIN, OR THAT EXTEND BEYOND THE DURATION HEREOF.

LIMITATION OF REMEDIES AND LIABILITIES:

YOUR SOLE AND EXCLUSIVE REMEDY UNDER THIS LIMITED WARRANTY SHALL BE PRODUCT REPAIR OR REPLACEMENT AS PROVIDED HEREIN.

UNDER NO CIRCUMSTANCES WILL JACKSON BE LIABLE FOR ANY INCIDENTAL OR CONSEQUENTIAL DAMAGES, OR FOR DAMAGES IN THE NATURE OF PENALTIES. JACKSON'S LIABILITY ON ANY CLAIM OF ANY KIND WITH RESPECT TO THE GOODS OR SERVICES COVERED HEREUNDER SHALL IN NO CASE EXCEED THE PRICE OF THE GOODS OR SERVICES OR PART THEREOF WHICH GIVES RISE TO THE CLAIM.

ITEMS NOT COVERED:

THIS WARRANTY DOES NOT COVER (1) ADJUSTMENTS INCLUDING, BUT NOT LIMITED TO, TIMER CAMS, THERMOSTATS, DOORS, TANK HEATER ADJUSTMENTS OR CLUTCHES; (2) AIR FREIGHT OR OVERNIGHT FREIGHT; (3) ANY AMOUNT EXCEEDING ORIGINAL PURCHASE PRICE; (4) CLEANING OF DRAIN VALVES, GAS LINES, RINSE/WASH NOZZLES, STRAINERS, SCREENS, OR SPRAY PIPES; (5) CLEANING OR DELIMING OF THE DISHACHINE OR ANY COMPONENT INCLUDING, BUT NOT LIMITED TO, WASH ARMS, RINSE ARMS AND STRAINERS; (6) CONDITIONS CAUSED BY THE USE OF INCORRECT (NON-COMMERCIAL) GRADE DETERGENTS; (7) CORROSION FROM CHEMICALS DISPENSED IN EXCESS OF RECOMMENDED CONCENTRATIONS; (8) COSMETIC DAMAGE, INCLUDING BUT NOT LIMITED TO, SCRATCHES, DENTS, CHIPS, AND OTHER DAMAGE TO THE DISHACHINE FINISHES, UNLESS SUCH DAMAGE RESULTS FROM DEFECTS IN MATERIALS AND WORKMANSHIP AND IS REPORTED TO JACKSON WITHIN (30) THIRTY DAYS FROM THE DATE OF INSTALLATION; (9) DAMAGE CAUSED BY LABOR DISPUTE; (10) DAMAGES RESULTING FROM IMPROPER CONNECTION TO UTILITY SERVICE; (11) DAMAGES RESULTING FROM WATER CONDITIONS, INADEQUATE OR EXCESSIVE WATER PRESSURE, ACCIDENTS, ALTERATIONS, IMPROPER USE, ABUSE, HANDLING, OVERLOADS, TAMPERING, IMPROPER INSTALLATION OR FAILURE TO FOLLOW MAINTENANCE AND OPERATING PROCEDURES; (12) DISCOLORATION, RUST OR OXIDATION OF SURFACES RESULTING FROM CAUSTIC OR CORROSIVE ENVIRONMENTS, INCLUDING, BUT NOT LIMITED TO, HIGH SALT CONCENTRATIONS, HIGH MOISTURE OR HUMIDITY, OR EXPOSURE TO CHEMICALS; (13) ELECTRIC BOOSTERS, FEED LINES, FLEX HOSE, FUSES, GARBAGE DISPOSALS, OR GAS PILOTS; (14) EXCESSIVE LIME, MINERAL, OR ALKALINE BUILDUP; (15) EXPENSES DUE TO DISCONNECTION, DELIVERY, RETURN AND REINSTALLATION; (16) FAILURE OF ELECTRICAL COMPONENTS DUE TO CONNECTION OF CHEMICAL DISPENSING EQUIPMENT INSTALLED BY OTHERS; (17) FAILURE OF FACILITY WATER HEATER TO MAKE TEMPERATURE; (18) FAILURE TO MAINTAIN WATER HARDNESS LOWER THAN 3.0 GRAINS, PH BETWEEN 7.0 AND 8.5 AND TOTAL DISSOLVED SOLIDS BELOW 250 PPM; (19) FAILURE TO COMPLY WITH LOCAL ELECTRICAL BUILDING CODES; (20) LEAKS OR DAMAGE RESULTING FROM SUCH LEAKS CAUSED BY THE INSTALLER, INCLUDING THOSE AT MACHINE TABLE CONNECTIONS, OR BY CONNECTION OF CHEMICAL DISPENSING EQUIPMENT INSTALLED BY OTHERS; (21) OPENING OR CLOSING OF UTILITY SUPPLY VALVES OR SWITCHING OF ELECTRICAL SUPPLY CURRENT; (22) PERFORMANCE OF REGULAR MAINTENANCE AND CLEANING AS OUTLINED IN THE OPERATOR'S GUIDE; (23) REMOVAL OR REINSTALLATION OF INACCESSIBLE DISHACHINES OR BUILT-IN FIXTURES THAT INTERFERE WITH SERVICING, REMOVAL OR REPLACEMENT OF THE DISHACHINE; (24) REPLACEMENT WEAR ITEMS INCLUDING, BUT NOT LIMITED TO, CURTAINS, DRAIN BALLS, DOOR GUIDES, GASKETS, O-RINGS, SEALS, SQUEEZE TUBES, AND BEARINGS; (25) RESIDENTIAL USE; (26) USE WITH UTILITY SERVICE OTHER THAN THAT DESIGNATED ON THE RATING PLATE.

REVISION HISTORY

Revision	Date	Made by	Process	Details
A	5-25-07	MAW	N/A	Release to Production
24	10-4-07	MAW	7934	Changed cover on power junction box.
10	5-20-09	ARL	QOF-339	Updated programming page diagram.
B	4-26-12	RLC	QOF-386	Updated location of door switch on schematic.
C	4-27-12	RLC	QOF-386	Added EnergyStar logo.
D	3-08-13	RLC	QOF-219	Updated company logo.
E	1-23-14	MHH	QOF-238	Added wiring change schematics. Removed "Stop" page. Updated warranty information.
F	3-12-14	MHH	8293	Removed page on programming chemical feeder pumps. Updated drawings for control box assembly, motor & pump assembly and incoming plumbing assembly. Added schematics and harness connections.
G	12-15-15	JH	N/A	Removed Delta 5D and all references to it. Changed P/N 05330-100-01-10 to 05330-011-61-34, item #3 on pg. 32.
H	4-22-16	JH	N/A	Changed drain connection information to 2 1/2" and changed NPT to "No Hub Connection" on pg. 2.
J	5-9-16	JH	8380	Changed Booster Tank Assembly view and applicable P/Ns to show thermostat change, pg. 32. Added schematic 09905-003-36-56-E to show thermostat change, pg. 37. Removed earlier versions. Changed Harness Connections diagram to show thermostat change, pg. 38.
K	1-3-17	JH	N/A	Updated to new manual format. Audited and corrected all P/Ns in the manual.
L	1-6-20	JH	8709	Corrected water line size to 1/2" on Operating Specs page. Removed unnecessary information from Electrical Requirements page and corrected motor HP. Updated Chemical Feeder Pump Components page. Changed complete motor assembly P/N on Motor page. Updated schematic to latest revision.
M	9-15-21	JH	8756	Replaced CAM timer with electronic cycle timer. Changed stand pipe P/N on Tub page.
N	12-13-21	JH	N/A	Updated water consumption per Energy Star 3.0 report.
P	5-6-22	JH	22-1197 22-1202	Updated Chemical Feeder Pumps section with black dot roller. Added in-line fuse for drain solenoid. Updated schematic.
Q	12-13-22	JH	8896 8899 8901	Added timer bracket to control box section. Updated peri-pumps with black components. Corrected item numbers and added splash shields in Tub section. Revised discharge hose assembly in Frame & Motor section. New door assembly. Updated schematic.
R	3-8-24	JH	8924	Updated Inlet Plumbing section.



Delta 5-E

Glasswasher dishmachine; low-temperature, chemical-sanitizing, with a sustaining heater and detergent, rinse-aid, and sanitizer chemical feeder pumps.

The manufacturer provides technical support for all of the dishmachines detailed in this manual. We strongly recommend that you refer to this manual before making a call to our technical support staff. Please have this manual open when you call so that our staff can refer you, if necessary, to the proper page. Technical support is not available on holidays.

Contact technical support toll free at 1-888-800-5672.

Technical support is available for service personnel only.

TABLE OF CONTENTS

GUIDES

Symbols	1
Abbreviations & Acronyms	1

SPECIFICATIONS

Machine Dimensions	2
Operating Specifications	3
Electrical Requirements	4

INSTALLATION

Installation Instructions	5
<i>Inspection</i>	5
<i>Unpacking</i>	5
<i>Leveling</i>	5
<i>Facility Hot Water Heater</i>	5
<i>Plumbing</i>	5
<i>Water Supply Connections</i>	6
<i>Pressure Regulator</i>	6
<i>Shock Absorber</i>	6
<i>Drain Line</i>	6
<i>Plumbing Check</i>	6
<i>Electrical Power Connections</i>	7
<i>Voltage Check</i>	7
<i>Surrounding Area</i>	7
<i>Temperature Setpoints</i>	7
<i>Chemical Feeder Equipment</i>	8
<i>Preparing Chemical Feeder Pumps</i>	8
<i>Priming Chemical Feeder Pumps</i>	8
<i>Cycle Timer Instructions</i>	9

OPERATION

Operation Instructions	13
<i>Preparation</i>	13
<i>Power Up</i>	13
<i>Initial Start-up</i>	13
<i>Ware Preparation</i>	15
<i>Daily Start-up</i>	15
<i>Washing a Rack of Ware</i>	15
<i>Operational Inspection</i>	16
<i>Shutdown & Cleaning</i>	16
Detergent Control	17
Deliming	18

TABLE OF CONTENTS

MAINTENANCE

Preventative Maintenance	19
--------------------------------	----

TROUBLESHOOTING

Troubleshooting	20
-----------------------	----

PARTS SECTION

Control Box	22
Chemical Feeder Pump Components	25
Peri-pump Box	26
Electrical Connection Box	27
Frame	28
Hood	29
Switch Panel	30
Tub	31
Frame & Motor	34
Motor	36
Sustaining Heater	37
Inlet Plumbing	38
Plumbing Options	39
Solenoid Valve Repair Kits	40
Door	41
Front Panel	42

SCHEMATICS

Delta 5-E 115 V, 60 Hz, 1-Phase	43
Delta 5-E Harness Connections	44

SYMBOLS



- Risk of Injury to Personnel



- Risk of Damage to Equipment



- Risk of Electrical Shock



- Caustic Chemicals



- Reference Data Plate



- Lockout Electrical Power

NOTICE

- Important Note



- Instructions Hyperlink

ABBREVIATIONS & ACRONYMS

ANSI - American National Standards Institute

GHT - Garden Hose Thread

GPG - Grains per Gallon

GPM - Gallons per Minute

HP - Horse Power

Hz - Hertz

ID - Inside Diameter

kW - Kilowatts

MCA - Minimum Circuit Ampacity

MOP - Maximum Overcurrent Protection

NFPA - National Fire Protection Association

NPT - National Pipe Thread

OD - Outside Diameter

PRV - Pressure Regulating Valve




PSI - Pounds per Square Inch

V - Volts

LEGEND

- A - Water Inlet (1/2" NPT)
- B - Drain Connection (2" NPT)
- C - Electrical Connection

All dimensions from the floor can be increased 2 3/4" using the machine's adjustable feet.



OPERATING SPECS Operating Capacity:

Racks per Hour (without load time)	39
Dishes per Hour	975
Glasses per Hour	1404
Gallons per Rack	1.15
Gallons per Hour	44.85

Operating Cycles (Seconds):

Wash Time	46
Rinse Time	25
Dwell Time	21
Total Cycle Time	92

Wash Tank Capacity (Gallons): 1.2

Water Temperatures (°F):

Minimum Wash Temperature	120
Minimum Rinse Temperature	120

(140 °F is recommended for both.)

Other Water Requirements:

Water Line Size (NPT)	1/2"
Drain Line Size (NPT)	2"
Flow Pressure (PSI)	20 ± 5

Minumum Chlorine Required (PPM): 50

NOTICE

Always refer to the machine data plate for specific electrical and water requirements. The material provided on this page is for reference only and is subject to change without notice.

NOTICE

**Electrical Requirements:**

Wash Motor HP	1
Sustaining Heater kW	2

All electrical ratings provided in this manual are for reference only. Always refer to the machine data plate to get exact electrical information for this machine. **All electrical work performed on machines should be done in accordance with applicable local, state, territorial, and national codes.** Work should only be performed by qualified electricians and authorized service agents.

**The Delta 5-E is designed so the wash motor is never running when the sustaining heater is on. Total Load is based on the higher of the two loads.*

Delta 5-E Electrical Characteristics

VOLTS	115
PHASE	1
FREQ	60
WASH MOTOR AMPS	10.0 A
SUST. HEATER AMPS	16.0 A
TOTAL LOAD	16.0 A*
MCA	18.5 A
MOP	25 A

INSPECTION

Do not throw away packaging if damage is evident!

Before installing the machine, check packaging and machine for damage. Damaged packaging might be an indication of damage to the machine. If there is any type of damage to both packaging and machine, do not throw away the packaging. The machine has been inspected at the factory before shipping and is expected to arrive in new, undamaged condition. However, rough handling by carriers or others might result in damage to the machine while in transit. If this occurs, do not return the machine to the manufacturer. Instead, contact the carrier and ask them to inspect the damage and complete an inspection report.

Contact the carrier within 48 hours of receiving the machine as well as the dealer that sold you the machine.

UNPACKING

The machine should be unpacked and removed from the pallet before installing. Open the front door and remove all materials from inside. Once unpacked, verify there are no missing parts. If a part is missing, contact the manufacturer immediately.

LEVELING

The machine is designed to operate while level. This is important to prevent any damage to the machine during operation and to ensure the best possible results. The machine comes equipped with adjustable bullet feet which can be turned using a pair of pliers. Verify the unit is level from front-to-back and side-to-side before making any electrical or plumbing connections.

FACILITY HOT WATER HEATER

The manufacturer does NOT endorse "Tankless On-demand" water heaters for use with their machines. The manufacturer DOES endorse, and highly recommends, the standard "Tank" style water heaters, sized to properly handle the water heating requirements of the facility.

PLUMBING



CAUTION! The plumber must flush the incoming water line!


A water hardness test must be performed.

All plumbing connections must be made to adhere to local, state, territorial, and national codes. The installing plumber is responsible for ensuring the incoming water lines are flushed of debris before connecting to the machine. Note that chips and materials from cutting processes can become lodged in the solenoid valves and prevent them from opening or closing. Any valves that are found to be fouled or defective because of foreign matter left in the water line, and any subsequent damage, are not the responsibility of the manufacturer.

A water hardness test must be performed. If water hardness is higher than 3 GPG, install a water softener or install the optional Scale Prevention System (SPS). See next section and Plumbing Options page for more information on the SPS.

WATER SUPPLY CONNECTIONS: WATER HARDNESS HIGHER THAN 3 GPG

If water hardness is higher than 3 GPG and a water softener is not being used, install the optional SPS into the water line between the facility water line and the machine water line (installed at the factory). See the Plumbing Options page for more information on the SPS. Observe proper inlet/outlet water directions. A water shut-off valve should be installed before installing the SPS to allow access for service.



WATER SUPPLY CONNECTIONS: WATER HARDNESS LOWER THAN 3 GPG

If water hardness is lower than 3 GPG, install the water supply line (1/2" ID pipe size minimum) to the machine's incoming water connection point using copper pipe (or order the 1/2" ID flexible hose kit offered by manufacturer). A water shut-off valve should be installed before installing the SPS to allow access for service.

PRESSURE REGULATOR

The manufacturer has an optional water pressure regulator (see Plumbing Options page) to accommodate areas where water pressure fluctuates or is higher than the recommended pressure. Take care not to confuse static pressure with flow pressure: static pressure is line pressure in a "no flow" condition (all valves and services are closed); flow pressure is the pressure in the fill line when the valve is opened during the cycle.

Take care not to confuse static pressure with flow pressure.

SHOCK ABSORBER

It is suggested that the optional shock absorber (see Plumbing Options page) be installed on the incoming water line. This prevents water hammer (hydraulic shock) from causing damage to the equipment.

DRAIN LINE

The machine drain requires a minimum 2" NPT piping that is pitched at least 1/4" per foot. There must also be an air-gap between the machine drain line and the floor sink or drain. If a grease trap is required by code, it should have a flow capacity of 5 GPM.

PLUMBING CHECK

After installing the incoming fill line and drain line, slowly turn on the water supply to the machine. Check for any leaks and repair as required. All leaks must be repaired before operating the machine.

ELECTRICAL POWER CONNECTIONS




Disconnect electrical power at the breaker or disconnect switch and tag-out in accordance with procedures and codes.

Electrical and grounding conductors must comply with the applicable portions of the National Electric Code ANSI/NFPA 70 (latest edition) and/or other electrical codes.

The data plate is located behind the door of the machine. Refer to the data plate for machine operating requirements, machine voltage, total amperage, and serial number.

Remove the connection box lid to install the incoming power lines. Install 1/2" conduit into the pre-punched holes in the back of the control box. Route power wires and connect to power block and grounding lug. Install the service wires to the appropriate terminals as they are marked on the terminal block. Install the grounding wire into the lug provided. It is recommended that "DE-OX" or another similar anti-oxidation agent be used on all power connections.



VOLTAGE CHECK



Apply power to the machine. Check the incoming power at the terminal block and ensure it corresponds with the voltage listed on the data plate. If not, contact a qualified service agency to examine the problem. Do not run machine if voltage is too high or too low. Shut off the service breaker and advise all proper personnel of the location of the breaker and any problems. Replace the connection box lid and tighten-down the screws.

SURROUNDING AREA

This is a commercial machine and reaches temperatures that can exceed those generated by a residential machine. Therefore, any surrounding countertops, cabinets, flooring material, and subfloor material must be designed and/or selected with these higher temperatures in mind.

NOTICE

Any damage to surrounding area that is caused by heat and/or moisture to materials that are not recommended for higher temperatures will not be covered under warranty or by the manufacturer.

TEMPERATURE SETPOINTS

The temperature setpoints on this unit have been set at the factory. They should only be adjusted by an authorized service agent.

CHEMICAL FEEDER EQUIPMENT



This equipment is not recommended for use with deionized water or other aggressive fluids. Use of deionized water or other aggressive fluids will result in corrosion and failure of materials/components and will void the manufacturer's warranty.

CAUTION! *Chlorine-based sanitizers can damage the machine if the chemical solution is too strong. Contact the chemical supplier for information.*

PREPARING CHEMICAL FEEDER PUMPS

This machine is supplied with detergent, rinse-aid, and sanitizer chemical feeder pumps.

Locate the open ends of the chemical tubes with the tube stiffeners and place each one in the appropriate container.

- Red Tubing = Detergent
- Blue Tubing = Rinse-aid
- White Tubing = Sanitizer


PRIMING CHEMICAL FEEDER PUMPS

Chemical feeder pumps need priming when the machine is first installed or if the chemical lines have been removed and air was allowed to enter.



CAUTION! *Water must be in the sump and wash tank before dispensing chemicals.*

1. Verify proper chemical tube stiffener inlet is in proper container.
2. Use prime switches located on the panel inside the door to prime each pump. The switches are clearly marked with the type of chemical.
3. To prime pumps, hold the switch until the chemical can be observed entering the sump.



WARNING! *Some dishwashing chemicals might cause chemical burns. Wear protective gear when handling these chemicals. If any skin contact occurs, follow the instructions provided with the chemicals.*

4. Detergent is dispensed as required during the wash cycle by the timer. The amount of detergent might need to be adjusted depending on water quality and type of detergent.
5. Rinse-aid is dispensed as required into the final rinse. The amount of rinse-aid might need to be adjusted depending on water hardness and results.
6. Sanitizer is dispensed into the final rinse. The amount of sanitizer might need to be adjusted depending on the concentration.

INSTALLATION

CYCLE TIMER INSTRUCTIONS


OVERVIEW

NOTICE

Machines with serial numbers before 21H396817 have the old CAM timer. See [previous manual](#).

The timer accepts user input and provides feedback on the status of the dishmachine.

Cycle steps are the different sub-cycles (fill, drain, etc.) of the total wash cycle.




POWERING ON

The display will read "JACKSON WWS" and the firmware version when powered on. This is the Default/Home screen.


- If inactive for 15 seconds the blue backlight will turn off.
- If inactive for 30 seconds the display will turn off.
- Inactivity timer will reset if any button is pushed.
- Push any button while inactive and the display will turn on and show the Home screen.

SELECTING MODEL

1. With the display on, press TIMER MODEL. Display will show "SELECT MODEL" and the currently-active model.



2. Select correct model using ARROW buttons under STEP DURATION.
3. Press SAVE/EXIT.



**Model
DELTA 5**

INSTALLATION

CHANGING CYCLE STEP TIMES


The first two steps (CYCLE and PUMP) are fixed and can't be adjusted. All other steps are adjustable.

Timing of the total wash cycle begins when START is pressed. Machine returns to IDLE after one full cycle.


Change is also saved if inactive for 10 seconds or any other button is pressed.

CYCLE TIMER INSTRUCTIONS


1. Press button for step being changed. The LED for that step will come on.




2. Change STEP START TIME or STEP DURATION using ARROW buttons (adjustments are made in 0.25-second increments).



3. Press SAVE/EXIT to save the change and exit.



4. Repeat with other steps as needed.
5. To review current settings for a given step, press button for that step during IDLE. Its current STEP START TIME and STEP DURATION will be displayed.




INSTALLATION

CYCLE TIMER INSTRUCTIONS


RESETTING TO FACTORY DEFAULTS

1. Press and hold CYCLE COUNT button and DOWN ARROW button (under STEP DURATION) simultaneously for 3–4 seconds.



2. Resets all settings to factory defaults for the active model. Cycle count is unaffected by the reset.
3. Firmware version on the Home screen shows "F" at the end, indicating the timer is now set to factory defaults for the active model.


Firmware version changes, so number will be different depending on when timer was installed.



"M" = Modified Timing
"F" = Factory Defaults

CHECKING CYCLE COUNT

1. Press CYCLE COUNT button. Cycle count will show on display.




INSTALLATION

CYCLE TIMER INSTRUCTIONS

PLANT TEST MODE

1. Press and hold CYCLE COUNT button and DOWN ARROW button (under STEP START TIME) simultaneously for 3–4 seconds.




After 15 seconds of no button being pressed, the timer exits the plant test mode.

If more than one input is on, the first letters of each will show (e.g. "Drain-DH" indicates the DRAIN output and DoorClosed and Heavy inputs are on).

2. Press and hold the DRAIN button. The DRAIN output stays on while the button is held. The output turns off when the button is released. Repeat for the other seven buttons (use SAVE/EXIT to activate CYCLE output, use CYCLE COUNT to activate PUMP output). Second row of display shows outputs and inputs that are active.


Outputs

Cycle
Wash
Drain
Fill
Sani
Deter
Rinse
Spare



Inputs
DoorClosed
Start

3. Plant test mode can also be used to prime chemicals if the machine has no priming function. Open door and press and hold the SANI button until sanitizer is seen entering the wash sump/tank and no air is in the line.




4. Repeat for DETER and RINSE AID buttons.


PREPARATION

Before operating the machine, verify the following:


- Strainers are clean and in place.



- Drain stopper is installed.



- Wash/rinse arm is screwed securely into place and end-caps are tight.
- Wash/rinse arm rotates freely.




POWER UP

To energize the machine, turn on power at the service breaker. The voltage should have been previously verified as correct. If not, the voltage must be verified before energizing the unit.


INITIAL START-UP

Before the heater element can be energized, the heater tank must be initially filled with water.

1. Press and hold FILL button until water overflows into the wash strainer, then release the button.



2. The heater tank is now filled with water.
3. Turn off the machine by pressing the ON/OFF button.



CAUTION! *Damage to the heater element will occur if the element is not submerged in water.*

INITIAL START-UP




Disconnect electrical power at the breaker or disconnect switch and tag-out in accordance with procedures and codes.



CAUTION! Water must be in the sump while the machine is running to avoid running the pump dry and causing damage to the pump seal.

After filling the heater tank, the heater element must be enabled. The machine is shipped from the factory with the heater element disabled. This is done to ensure that the heater element is not damaged by energizing the element without the element being submerged in water. To enable the heater element:

1. Disconnect electrical power and remove the control box cover.



2. Connect the tagged white/blue wires.



3. Replace the control box cover and reconnect electrical power.
4. Press the ON/OFF button. The heater element will energize to sustain water temperature.

If the water level is not between the lines on the drain stopper, it will require adjustment. Check to ensure that the recommended water pressure is being supplied to the machine (20 ± 5 PSI). If the water pressure is correct, the timer needs adjustment. See Cycle Timer Instructions section.

The machine runs a complete cycle to drain and fill. If the machine fails to drain, the water will build-up inside the tub. After the initial fill, the rinse water for the current cycle will mix with the wash water for the next cycle.


WARE PREPARATION

Proper preparation of ware is essential for the smooth and efficient operation of the machine, resulting in fewer rewashes and less detergent used. Any ware loaded inside the machine should have all solid food waste and scraps removed. Ware should be sprayed-down before being placed in the machine.

Place cups and glasses upside-down in racks so they do not hold water during the cycle. Presoak flatware in warm water to assist in removal of stuck-on material. Load plates and saucers in the same direction.

DAILY START-UP


1. Ensure items in the Preparation section have been verified.
2. Verify chemical levels are correct.
3. Ensure power is on and the tub has filled to the correct level.
4. Push START button: the unit will start, run through the cycle, and shut off automatically.




5. Repeat this two more times.
6. The machine is now ready for operation.

WASHING A RACK OF WARE

1. Open door.
2. Place a rack of ware into the machine.



3. Press and hold START button until the cycle starts (about two seconds).
4. After cycle light goes off, the cycle is complete.



5. Open door and remove the rack.

OPERATIONAL INSPECTION


As the workday progresses, operators should regularly inspect the strainers to ensure they have not become clogged. If the strainers become clogged, it will reduce the washing capability of the machine.

SHUTDOWN & CLEANING




CAUTION! Do NOT beat strainers to remove soil and debris!


1. Turn machine off by pushing ON/OFF button.
2. Remove drain stopper and allow tub to drain.




3. Remove and clean the strainers.




4. Unscrew wash/rinse arm from its manifold.



5. Verify nozzles and arm are free from obstruction. If clogged, remove end-caps, clean nozzles with a brush, and flush with fresh water.
6. Replace end-caps and tighten with screwdriver.



7. Spray or wipe out interior of machine.



8. Replace wash/rinse arm.
9. Ensure all strainers are clean and securely in place.
10. Replace drain stopper.
11. Use stainless steel polish to protect outside of machine.

**DETERGENT
CONTROL**

Detergent usage and water hardness are two factors that greatly contribute to the machine's operating efficiency. Using the proper amount of detergent can become a source of substantial savings. A qualified water-treatment specialist can determine what is needed for maximum efficiency from the detergent.

- Hard water greatly affects the performance of the machine, causing the amount of detergent required for washing to increase. If the machine is installed in an area with hard water, the manufacturer recommends the installation of water treatment equipment.
- Deposited solids from hard water can cause spotting that will not be removed with a drying agent. Treated water will reduce this occurrence.
- Treated water might not be suitable for use in other areas of operation and it might be necessary to install a water treatment system for the water going to the machine only. Discuss this option with a qualified water treatment specialist.
- Properly train operators on how much detergent is to be used per cycle. Meet with a water treatment specialist and chemical supplier to discuss a complete training program for operators.
- Water temperature is an important factor in ensuring the machine functions properly, and the machine's data plate details what the minimum temperatures must be for the incoming water supply, the wash tank, and the rinse tank. If minimum requirements are not met, it's possible that dishes will not be clean or sanitized.
- Instruct operators to observe the required temperatures and to report when they fall below the minimum allowed. A loss of temperature can indicate a larger problem.




DELIMING To maintain the machine at its optimum performance level, lime and corrosion deposits must be removed. The frequency for deliming will be based on water conditions. A deliming solution is available from your chemical supplier. Read and follow all instructions on the label.


If this machine is equipped with the SPS and lime is becoming a frequent problem, the cartridge needs to be replaced. See the Plumbing Options page to order a replacement.

To delime the machine:


1. Turn the machine on by pressing the ON/OFF button.




2. Press and hold the FILL button until water overflows into the wash strainer.



3. Add deliming solution per supplier's instructions.
4. Close door.
5. Flip NORMAL/DELIME switch to DELIME.



6. Run machine the period of time recommended by chemical supplier.
7. Wait five minutes, then inspect inside of the machine. If the machine is not delimed, run again.
8. Flip NORMAL/DELIME switch to NORMAL.



9. Run two cycles to remove residual deliming solution.

PREVENTATIVE MAINTENANCE

The manufacturer highly recommends that any maintenance and repairs not specifically discussed in this manual only be performed by qualified service personnel. Performing maintenance on the machine may void a warranty.

By following the operating and cleaning instructions in this manual, users should get the most efficient results from the machine. As a reminder, here are some steps to ensure that the machine is used properly:




CAUTION! Do NOT beat strainers to remove soil and debris!


- Ensure water temperatures match those listed on the machine data plate (behind the door).
- Remove as much soil as possible from ware before loading into racks.
- Ensure all strainers are in place and free of soil and debris before operating the machine. To clean strainers, wipe them out with a rag and rinse under a faucet. A toothpick can be used to dislodge any stubborn debris. Do not beat strainers on waste cans; once bent they will not work properly.
- If hard water is present, install a water softener or SPS into the water line connecting to the machine (see Plumbing section).
- Ensure wash/rinse arm is secure in the machine before operating.
- Ensure the drain stopper is in place before operating.
- Do not overfill racks.
- Ensure glasses are placed upside-down in the rack.
- Ensure all chemicals being injected into the machine have been verified at the correct concentrations.
- Clean out the machine at the end of every workday per the Shutdown and Cleaning section.
- Follow all safety procedures, whether listed in this manual or put forth by local, state, or national codes/regulations.


PROBLEM	POSSIBLE CAUSE	REMEDY
Water overflow from bottom of door.	1. Clogged drain. 2. Machine not level. 3. Excessive inlet pressure. 4. Detergent foaming. 5. Wash/rinse arm end-cap missing. 6. Excessive fill time.	1. Remove obstruction. 2. Level machine or increase height to the front. 3. Install pressure reducing valve or adjust if one is present. Ensure flow meets data plate specification. 4. Reduce detergent quantity. 5. Replace. 6. Adjust timer fill time (see Initial Start-up section).
Wash motor doesn't operate on delime wash.	1. Loose or broken wires. 2. Defective delime switch. 3. Defective motor starting relay.	1. Reconnect or replace wires in motor. 2. Verify delime switch triggers input on PLC. If not, check wiring/replace membrane. 3. Replace.
Motor operates on delime wash but not on automatic.	1. Defective circuit in delime switch. 2. Loose or broken wires.	1. Replace switch. 2. Tighten and/or replace.
No water comes through the arm when the "FILL" switch is depressed.	1. Water not turned on. 2. Defective solenoid valve.	1. Turn water on. 2. Replace solenoid valve.
Little or no water coming through the rinse assemblies.	1. Limed-up rinse heads or piping. 2. Low water pressure.	1. Delime rinse heads. 2. Increase pipe size to machine. Adjust pressure regulator.
Rinse water runs continuously with breaker turned off.	1. Defective plunger in solenoid valve. 2. Defective diaphragm in solenoid valve.	1. Replace. 2. Replace diaphragm.

PROBLEM	POSSIBLE CAUSE	REMEDY
Wash temperature not at required reading.	1. Check that white/blue wires are connected. 2. Defective thermometer. 3. Defective thermostat. 4. Sustaining heater defective. 5. Defective heater contactor (R2). 6. Incoming inlet water temperature below required minimum. 7. Defective heater delay relay (R4)	1. See Initial Start-up section. 2. Replace. 3. Adjust or replace thermostat. 4. Replace heater element. 5. Replace. 6. Adjust. 7. Replace.
Rinse water not at required temperature range.	1. Check that white/blue wires are connected. 2. Defective thermometer. 3. Defective thermostat. 4. Incoming rinse water does not meet minimum criteria indicated on machine data plate	1. See Initial Start-up section. 2. Replace. 3. Adjust or replace thermostat. 4. Adjust as required.
No indication of pressure.	1. Water turned off. 2. Pressure gauge defective.	1. Turn water on. 2. Replace pressure gauge.


**NOTICE**

*Machines with serial numbers before 21H396817 have the old CAM timer. See [previous manual](#).



**NOTICE**


*Machines with serial numbers before 21H396817 have the old CAM timer. See [previous manual](#).




ITEM	QTY	DESCRIPTION	PART NUMBER
		Complete Control Box Assembly	05700-003-36-55
1	1	Control Box Weldment	05700-003-09-42
2	1	Control Box Cover	05700-003-30-54
3	1	Decal, Warning - Disconnect Power	09905-004-08-16
4	4	Screw, 10-32 x 1/2" Long, Phillips Tusshead	05305-011-39-36
5	1	Decal, Peri-pump Prime	09905-003-32-56
6	1	Switch, Delime/Normal	05930-301-21-18
7	1	Detergent/Rinse-aid Pump Prime Switch	05930-011-35-27
8	1	Sanitizer Pump Prime Switch	05930-111-38-21
9	1	Locknut, 1/4-20 SS Hex with Nylon Insert	05310-374-01-00
10	1	Washer, 1/4-20 SS	05311-174-01-00
11	2	Contactor	05945-109-05-69
12*	1	Timer, Electronic Cycle	05700-004-88-53
13	4	Fitting, Conduit, Heyco 1/2"	05975-011-49-03
14	1	Fitting, 1/2" Straight Snap-in	05975-003-33-27
15	5	Clamp, 5/8" Nylon	04730-011-39-01
16	2	Relay, 2-Pole	05945-111-35-19
17	1	Terminal Board	05940-021-94-85
18	1	Harness, Switch Panel	05700-003-35-37
19	1	Fitting, 1/2" 90-Degree Snap-in	05975-003-33-28
20	1	Conduit, 1/2" x 40"	05700-003-35-48
21	1	Cycle Counter	05990-111-35-38
22	2	Screw, 4-40 x 1/4" Phillips Pan Head	05305-002-32-38
23	1	Terminal Board	05940-002-78-97
24	1	Terminal Board	05940-001-97-91
25	1	Decal, Terminal Board 8-Position	09905-003-09-30
26	16	Locknut, 10-24 SS Hex with Nylon Insert	05310-373-01-00
27	6	Locknut, 6-32 SS Hex with Nylon Insert	05310-373-03-00
28	1	Harness, Wash Pump	05700-003-35-34
29	1	Harness, Drain Solenoid	05700-003-35-36
30	1	Harness, Peri-pump	05700-003-35-35
31	1	Conduit, 1/2" x 17" (not shown)	05700-003-35-49
32	1	Bracket, Timer	05700-004-88-57

NOTICE


**Machines with serial numbers before 21H396817 have the old CAM timer. See [previous manual](#).*




ITEM	QTY	DESCRIPTION	PART NUMBER
1	2	Pump Housing	04320-111-37-09
2	4	Screw, 8-32 x 3/8" Phillips	05305-011-37-07
3	1	Roller, Plastic	04320-002-82-28
4	2	Pump Cover	04320-111-37-08
5	8	Screw, 6-32 x 3/4" Phillips	05305-011-37-05
6	4	Screw, 8-32 x 1/2" Phillips	05305-011-37-06
7	1	Tube, Squeeze, 8"	05700-003-22-89
8	1	Motor, 14 RPM	04320-111-35-13
9	1	Motor, 36 RPM	04320-111-35-14




ITEM	QTY	DESCRIPTION	PART NUMBER
1	2	Peri-pump Assembly, 36 RPM	05700-004-71-60
2	1	Peri-pump Assembly, 14 RPM	05700-004-71-61
3	1	Drip Channel	05700-003-32-89
4	1	Peri-pump Box	05700-003-32-00
5	1	Peri-pump Box Cover	05700-003-33-80
6	1	Fitting, Conduit, Heyco 1/2" (behind box)	05975-011-65-51
7	1	Clamp, 5/8" Nylon (inside box)	04730-011-39-01
8	1	Clamp, 1" Nylon	04730-002-41-88
9	5	Screw, 10-32 x 1/2"	05305-011-39-36
10	3	Locknut, 10-24 SS Hex w/Nylon Insert	05310-373-01-00
11	3	Tube Stiffener (not shown)	05700-002-66-49
12	1	Tubing, 1/4" OD x 60" Long, Blue	05700-002-52-34
13	1	Tubing, 1/4" OD x 60" Long, White	05700-002-52-33
14	1	Tubing, 1/4" OD x 60" Long, Red	05700-011-63-18
15	1	Terminal Board (inside box)	05940-001-97-91
16	1	Tubing, 1/4" OD x 120" Long, Blue	05700-011-37-17
17	1	Tubing, 1/4" OD x 120" Long, White	05700-011-37-13
18	1	Tubing, 1/4" OD x 120" Long, Red	05700-011-37-15




ITEM	QTY	DESCRIPTION	PART NUMBER
1	1	Box, Power Junction Weldment	05700-003-30-58
2	1	Terminal Block Spacer	05700-011-40-05
3	1	Terminal Block	05940-500-09-61
4	1	Locknut, 6-32 with Nylon Insert	05310-373-03-00
5	5	Locknut, 10-24 with Nylon Insert	05310-373-01-00
6	1	Lug, Ground	05940-200-76-00
7	1	Decal, Power Connection	09905-011-47-64
8	1	Decal, Warning to Disconnect Power	09905-004-08-16
9	1	Screw, 10-32 x 1/2" Long, Phillips Trusshead	05305-011-39-36
10	2	Decal, Copper Conductors Only	09905-011-47-35
11	1	Cover, Solenoid Box	05700-003-46-72




ITEM	QTY	DESCRIPTION	PART NUMBER
1	4	Adjustable Foot	05340-002-14-55
2	1	Plate, Hinge Weldment	05700-003-10-11
3	1	Washer, Hinge Weldment	05700-002-54-62
4	1	Spacer, PB Bolt	05700-000-29-40
5	1	Clamp, Pipe	05700-000-35-05
6	8	Washer, 1/4-20 SS	05311-174-01-00
7	1	Keeper, Door Panel Latch	05700-003-09-31
8	4	Locknut, 1/4-20 SS Hex with Nylon Insert	05310-374-01-00
9	5	Nut, Hex 1/4-20	05310-274-01-00
10	1	Heater Mounting Plate Weldment	05700-002-51-93
11	1	Bracket, Temperature Gauge	05700-003-14-53
12	1	Bolt, 1/4-20 x 1/2"	05305-274-02-00
13	1	Bracket, Manifold Position Tube	05700-011-34-63



ITEM	QTY	DESCRIPTION	PART NUMBER
1	1	Switch, 115 V Reed	05930-002-36-80
2	1	Bracket, Limit Switch	05700-021-71-18
3	4	Locknut, 10-24 with Nylon Insert	05310-373-01-00
4	2	Clamp, Pipe 5/8"	05700-000-35-06
5	2	Rack Rail Weldment	05700-002-45-67
6	2	Washer, 1/4"-20 I.D.	05311-174-01-00
7	1	Gasket, Switch Panel	05330-100-10-00




ITEM	QTY	DESCRIPTION	PART NUMBER
		Complete Switch Panel Assembly	05700-003-24-38
1	1	Switch Panel Weldment	05700-003-24-36
2	2	Switch, Prime Assembly	05700-003-14-91
3	1	Switch, On/Off Assembly	05700-003-14-92
4	1	Light, Amber	05945-504-06-18
5	1	Light, Red	05945-504-07-18
6	1	Decal, Switch Panel	09905-003-08-63
7	1	Fitting, .25-.546	05975-011-65-51
8	3	Plug, 3/4" Hole	04730-011-60-21
9	6	Locknut, 10-24 with Nylon Insert	05310-373-01-00
10	6	Washer	05311-176-02-00
11	1	Terminal Board (not shown)	05940-001-97-91




ITEM	QTY	DESCRIPTION	PART NUMBER
1	1	Lower Manifold Weldment	05700-002-45-51
2	2	Manifold Gasket	05700-111-35-03
3	1	Drain Seat Insert	05700-004-37-18
4	1	Spillway Gasket	05700-111-34-52
5	1	Spillway Weldment	05700-003-52-13
6	23	Locknut, 1/4-20 SS Hex with Nylon Insert	05310-374-01-00
7	1	Manifold O-Ring	05330-111-35-15
8	1	Modified Casting Wedge	09515-011-46-61
9	2	Bolt, 3/8-16 x 1 1/4" SS	05305-276-10-00
10	2	Washer, 3/8" Bevel-Square Iron	05311-011-35-36
11	2	Lockwasher, 3/8"	05311-276-01-00
12	2	Nut, 3/8-16 SS Hex	05310-276-01-00
13	1	Complete Wash Arm Assembly	05700-021-39-23
13a	1	Wash Arm End-cap	05700-003-31-59
14	1	Sump Strainer	05700-002-60-50
15	1	Stand Pipe	05700-004-19-51
16	1	Complete Drain Link Assembly	05700-002-45-52
16a	1	Drain Link	05700-002-40-83
16b	1	Nut, Hex, 5/16-18	05310-275-01-00
16c	1	Drain Link Connector	05700-002-38-10
17	1	Hair Pin, 1/8" to 1"	05315-011-60-09
18	1	Fill Tube Weldment	05700-002-45-61
19	18	Washer, 1/4-20 ID	05311-174-01-00
20	3	Chemical Tube Grommet	05325-002-42-65
21	2	Complete Door Pivot Plate Assembly	05700-003-54-46
22	3	Bolt, 1/4-20 x 1/2"	05305-274-02-00
23	6	Screw, 1/4-20 x 5/8"	05305-274-24-00
24	1	Air-gap Weldment	05700-003-23-48
25	1	Halo Assembly	05700-003-23-49
25a	1	Halo Weldment	05700-003-16-64
25b	4	Spray Nozzle and Receptacle	04730-002-55-61
26	1	Gasket, Air-gap	05330-003-24-17


ITEM	QTY	DESCRIPTION	PART NUMBER
27	2	Clamp, 1" Nylon (not shown, located on tub bottom)	04730-002-41-88
28	1	Drain Solenoid Box Assembly	05700-003-09-61
28a	1	Solenoid Box Weldment	05700-003-35-88
28b	1	Drain Solenoid, 115 V	04810-200-11-00
28c	4	Locknut, 10-24 with Nylon Insert	05310-373-01-00
28d	1	Solenoid Box Cover	05700-003-30-25
28e	1	Decal, Warning to Disconnect Power	09905-004-08-16
28f	1	Fuse Holder Assembly, In-line	05920-004-55-23
		Fuse, In-line 1 A (not shown)	05920-004-55-14
29	1	Splash Shield, Right	05700-005-03-84
30	1	Splash Shield, Left	05700-005-03-85



ITEM	QTY	DESCRIPTION	PART NUMBER
1	1	Discharge Tube Connector	05700-011-70-34
2	1	Pump Suction Hose	05700-002-40-82
3	1	Discharge Hose Assembly	05700-002-45-58
4	1	Wash Restrictor	05700-002-84-69
5	1	Accumulator Strainer Weldment	05700-003-33-25
6	1	Accumulator Weldment	05700-002-51-95
7	8	Bolt, 1/4-20 x 1/2"	05305-274-02-00
8	18	Locknut, 1/4-20 SS Hex with Nylon Insert	05310-374-01-00
9	18	Washer, 1/4-20 SS	05311-174-01-00
10	1	Hose Clamp, 13/16" to 1 1/2"	04730-719-06-09
11	3	Hose Clamp, 1 1/16" to 2 1/4"	04730-719-18-00
12	1	Gauge, Thermometer	06685-111-68-48




ITEM	QTY	DESCRIPTION	PART NUMBER
		Complete Pump & Motor Assembly	06105-004-28-95
1	1	Motor Only	06105-004-32-03
2	1	Case O-Ring Seal Plate	05330-002-81-83 05700-002-81-87
3	1	Mechanical Seal	05330-002-34-22
4	4	Case Capscrew	05305-002-81-88
5	1	Pump Casing	05700-002-85-01
6	1	Shim Kit	05700-002-82-58
7	1	Impeller Assembly	05700-002-81-86
8	1	Drain Plug (not shown)	04730-002-81-89



ITEM	QTY	DESCRIPTION	PART NUMBER
1	1	Heater Tank	05700-003-25-40
2	1	Heater Gasket	05330-011-61-34
3	1	Sustaining Heater	04540-002-45-13
4	4	Lockwasher, Split 5/16"	05311-275-01-00
5	4	Nut, Hex 5/16-18	05310-275-01-00
6	2	Nut, Lock 6-32 Hex with Nylon Insert	05310-373-03-00
7	2	Spacer, 1/4" OD x 9/32"	09330-004-34-91
8	1	Thermostat, Elan Electric (Dual)	06685-004-17-27
9	1	Cover, Heater Box	05700-004-34-90
10	1	Decal, Warning to Disconnect Power	09905-004-08-16
11	1	Probe, Thermistor	06685-004-17-26
12	1	Probe Fitting, Thermostat	05310-924-02-05


Complete Inlet Plumbing Assembly
05700-002-45-57




ITEM	QTY	DESCRIPTION	PART NUMBER
1	1	Y-Strainer	04730-217-01-10
2	1	Nipple, Close, 1/2" NPT, Brass	04730-207-15-00
3	1	Elbow, 1/2"	04730-406-01-01
4	1	Elbow, 90-Degree (CU to MSPS)	04730-406-32-01
5	1	Union, 1/2"	04730-412-05-01
6	1	Adaptor, 1/2" Fitting (CU to Male)	04730-401-03-01
7	1	Tube, Copper, 1/2" x 4 1/4"	05700-001-01-60
8	2	Tube, Copper, 1/2" x 1 1/4"	05700-001-08-28
9	1	Valve, Solenoid, 1/2" NPT, 115 V	04810-003-71-55
10	1	Fitting, 1/2", 90-Degree	05975-003-35-32
11	1	Conduit, 1/2" Flex	05975-003-33-36
12	1	Fitting, 1/2", Straight	05975-003-33-27




SHOCK ABSORBER (WATER ARRESTOR) OPTION




PRESSURE REGULATOR OPTION



SCALE PREVENTION SYSTEM (SPS) OPTION





Complete 110 Volt Solenoid Valve Assembly, 1/2"

04810-100-12-18




Coil & Housing only, 1/2"

06401-003-07-43


Complete Door Assembly
05700-005-05-95

NOTICE

Machines with serial numbers before 22H409822 have the old door. See [earlier manual](#).





ITEM	QTY	DESCRIPTION	PART NUMBER
1	1	Magnet	05930-002-88-42
2	1	Magnet Cover	05700-004-07-38
3	2	Locknut, 6-32 SS Hex with Nylon Insert	05310-373-03-00
4	1	Bolt, 1/4-20 Eye	05306-002-55-59
5	1	Nut, Hex 1/4-20	05310-274-01-00
6	1	Locknut, 1/4-20 Hex with Nylon Insert	05310-374-01-00
7	1	Spring, Door	05340-011-44-58
8	1	Door	05700-005-05-96



ITEM	QTY	DESCRIPTION	PART NUMBER
		Complete Panel Assembly	05700-003-09-53
1	1	Panel Weldment	05700-003-09-54
2	1	Handle	05340-001-96-30









Jackson WWS, Inc. • 6209 N. US Hwy 25E • Gray, KY 40734 USA
1.888.800.5672 • www.jacksonwws.com

Delta 5-E Manual • 07610-003-37-08-R